6. Rate of fees allowed to be collected:—

	Rs.	a.	p.
On one head load	0	0	3
On one animal load	0	0	6
One single bullock cart load	0	1	0
One double bullock cart load	0	2	0

P. VENKAPPIAH,
For *President.*

HASSAN DISTRICT BOARD.

TENDER NOTICE.

Dated 18th April 1927.

Notice is hereby given that sealed tenders will be received by the undersigned till 2 P.M., on 30th April 1927, for constructing an out-house to the Musafirkhana at Belur.

2. No tender will be received after the date and hour above entered.

3. Tenders to be superscribed "Tender for constructing an out-house to the Musafirkhana at Belur."

4. No tender will be received unless accompanied by a deposit of Rs. 100 in cash, currency notes or Treasury receipts.

5. The estimate and plans, will be available at the Office of the President, District Board, Hassan, between 11 A.M. and 5 P.M. on all working days.

6. The President does not bind himself to accept the lowest or any tender or to assign any reason for not accepting any tender.

7. The deposit of the successful tenderer will be retained and will be forfeited by the District Board if he fails to complete the contract satisfactorily and in time and by executing necessary agreement within a week from the date of acceptance and he will be bound to make good to the District Board any loss which may arise from such cessation.

8. Work should be started within fifteen days from the date of notification of the acceptance.

9. Any other conditions he may wish to state should also be included in his tender.

Approximate quantities of work to be done are noted below:—

	Items of work	Per	Rate	Quantity	Cost	Total
1	Earthwork excavating foundation ...	C.yd.		16		
2	Burnt stone in mud filling in foundation.	C.ft.		432		
3	Burnt stone in chunam basement ...	„		216		
4	Burnt brick in mud superstructure...	„		1,463		
5	Woodwork (honne or Nandi wood) doors and windows complete (inner dimensions).	S.ft.		89½		
6	Jungle wood wrought and put up honne or nandi.	C.ft.		74		
7	Mangalore tiles over strong jungle wood reepers, etc., complete.	Sqrs.		9·36		
8	Mangalore Ridge tiles set in mortar	R.ft.		36		
9	New stone slabs roughly dressed 5" thick.	S.ft.		108		
10	Chunam plastering inside ...	Sqr.		19·54		
11	Chunam borders over roof ...	R.ft.		48		
12	Chacolate painting to doors and windows.	Sqr.		1·79		
13	Jelly concrete to flooring and plastering.	„		3·93		
14	Constructing bath room pit and drain	Lump sum				
15	White and colour washing two coats	Sqr.		19·54		
16	Chimney for the kitchen ...	Lump sum				

N. S. NANJUNDIYA H,
President.